TENDER OPPORTUNITY

The Village of Debden invites tenders to reshingle the roof of the **Debden Centennial Hall** located at #120 Main Street Debden and the **Debden Community Center** located at #204 2nd Avenue **East** Debden, SK.

Please obtain tender documents from:

Village of Debden #204 2nd Avenue East Debden, Saskatchewan S0J0S0 Or online at <u>debden.ca</u>

Lowest or any tender not necessarily accepted. Only those tenders accepted will be notified. Contractors must provide proof of Contractor's Liability Insurance, Statutory Workers' Compensation Board coverage as required by law, and current business license with the Village of Debden is required.

Tenders close at 10:00 a.m. on October 7, 2025.

* Tenders must be clearly labeled "*Tender for Centennial Halland Community Centre*" on the outside of the envelope and envelope must be sealed with signature and date written across seal of envelope. Tenders can be dropped off or mailed to:

Village of Debden PO Box 400 #204 2nd Avenue East Debden, Saskatchewan S0J0S0 Tender submission to Re-shingle the Debden Centennial Hall and the Debden Community Centre:

Tenders close at 10:00 a.m. October 7, 2025 - Lowest or any tender not necessarily accepted.

We submit a	tender to do the above descr	ibed job.					
Contractor N	ame						
Address			-				
Bid		(\$)				
Work start da	ate:						
Work Compl	etion Date:						
The successf	ul bid will include all consid	erations as listed below:					
The successful bid will include all considerations as listed below: 1) To provide all necessary tools, equipment, services, materials and labour to execute and complete in a satisfactory and workmanlike manner the removal of the current shingles to be replaced with 30 year shingles; 2) Be responsible for the disposal of the old shingles at Highway 55 Waste Management Landfill which is to be included in the tender submission; 3) Estimated start and finish time. 4) Site shall be secured at all times for the health and safety of the public; 5) Provide a copy of Contractors' Public Liability Insurance to cover any occurrence of bodily injury death, property damage; 5) Payment of applicable municipal business license fee; 6) Statutory Workers' Compensation Board coverage as required by law; and 7) The contractor shall be responsible for adherence to initiating, maintaining and supervising all safety precautions and programs in connection with the work to ensure: a) no person, property, right, easement or privilege is injured, damaged or infringed by reason of the contractor's activities in performance of the contract; b) pedestrian and other traffic on any public or private road is not endangered by the method or means of its performance c) the health and safety of all persons employed in the performance of the work is not endangered by the method or means of its performance.							
		for Centennial Hall and Community Centre th signature and date written across seal of e					
Please includ S0J 0S0	le this form with your tender	as outlined above to PO Box 400 or #204 2	nd Avenue East, Debden, SK				
Contractor si	gnature	Date					

Bidders may attach a breakdown of supplies and quantities or any other information that may aid the Village of Debden awarding the tender.

Location #1

Debden Community Centre

#204 2nd Avenue East

Information below is provided as an **Estimate Only** as provided by SGI and should only be used as a minimum guideline for works completed to submit tender. Contractors are encouraged to do a complete site evaluation before submitting tender bid.



IMG_5083

Date Taken: 8/14/2025



2-IMG_5084

Date Taken: 8/14/2025



3-LAYERSDate Taken: 8/14/2025




4-ROOF PITCHDate Taken: 8/14/2025



27-RIGHT SLOPE

Date Taken: 8/14/2025

INDUSTRIAL EXHAUST VENTS ON ROOF APPEAR NOT DAMAGED



28-RIGHT SLOPE

Date Taken: 8/14/2025

INDUSTRIAL EXHAUST VENTS ON ROOF APPEAR NOT DAMAGED





29-RIGHT SLOPE

Date Taken: 8/14/2025

INDUSTRIAL EXHAUST VENTS ON ROOF APPEAR NOT DAMAGED



30-FRONT SLOPE

Date Taken: 8/14/2025

FRONT SLOPE HAS NO VISIBLE



31-FRONT SLOPEDate Taken: 8/14/2025
METAL GAUGE



32-FRONT SLOPE

Date Taken: 8/14/2025

FRONT SLOPE HAS NO VISIBLE





33-FRONT SLOPE

Date Taken: 8/14/2025 FRONT SLOPE HAS NO VISIBLE HAIL DAMAGE



34-FRONT SLOPE

Date Taken: 8/14/2025

FRONT SLOPE HAS NO VISIBLE



Date Taken: 8/14/2025 OVERVIEW



40-FRONT ELEVATION

Date Taken: 8/14/2025

FRONT ELEVATION DOWNSPOUT

HAS HAIL DAMAGE



Date Taken: 8/14/2025 FRONT ELEVATION DOWNSPOUT HAS HAIL DAMAGE



42-FRONT ELEVATION

Date Taken: 8/14/2025

FRONT ELEVATION DOWNSPOUT

HAS HAIL DAMAGE





Date Taken: 8/14/2025

REMAINING ITEMS ON
ELEVATION HAVE NO VISIBLE
HAIL DAMAGE



46-FRONT ELEVATION


Date Taken: 8/14/2025 REMAINING ITEMS ON ELEVATION HAVE NO VISIBLE HAIL DAMAGE

QUANTITY	UNIT	TAX	O&P	RCV AGE/	E/LIFE			
1. Asphalt starter - universal starter course								
536.52 LF				0/	0/20 yrs			
2. Tear off composition	shingles - 3 tab	(no haul off)						
89.67 SQ				0/	0/25 yrs			
3. Laminated - comp. sh	ingle rfg w/o	ut felt						
98.67 SQ				0/	0/30 yrs			
4. Drip edge								
789.33 LF				0/	0/35 yrs			
5. Roofing felt - 15 lb.								
77.28 SQ				0/	0/20 yrs			
6. lee & water barrier								
1,609.55 SF				0/	0/30 yrs			
7. Flashing - pipe jack								
2.00EA				0/	0/35 yrs			
8. Hip/Ridge cap - cut f	rom 3 tab - cor	nposition shin	igles					
101.43 LF	4.25			0/	0/25 yrs			
9. R&R Furnace vent - r	ain cap and sto	rm collar, 6"						
1 unit								
						=		
10. R&R downspout - al	uminum - up to	5"*						
20 LF				0/2:	25 yrs			
	Dek	oris Remova	l					

^{11.} Dumpster load - Approx. 40 yards, 7-8 tons of debris

Grand Total Areas:

5,094.22	SF Walls	0.00	SF Ceiling	5,094.22	SF Walls and Ceiling
0.00	SF Floor	0.00	SY Flooring	850.11	LF Floor Perimeter
0.00	SF Long Wall	0.00	SF Short Wall	0.00	LF Ceil. Perimeter
0.00	Floor Area	0.00	Total Area	0.00	Interior Wall Area
5,094.22	Exterior Wall Area	850.11	Exterior Perimeter of		
			Walls		
0.220.20		02.20	N. 1 CC	700.22	T (ID ') I d
9,328.28	Surface Area	93.28	Number of Squares	/89.33	Total Perimeter Length
101.43	Total Ridge Length	0.00	Total Hip Length		



Location #2

Centennial Hall

#120 Main Street

Information below is provided as an **Estimate Only** as provided by SGI and should only be used as a minimum guideline for works completed to submit tender. Contractors are encouraged to do a complete site evaluation before submitting tender bid.



Date Taken: 8/14/2025

OVERVIEW



32-FRONT ELEVATION

Date Taken: 8/14/2025

FRONT ELEVATION GUTTER HAS



Date Taken: 8/14/2025

FRONT ELEVATION GUTTER HAS

HAIL DAMAGE



36-FRONT ELEVATION

Date Taken: 8/14/2025

FRONT ELEVATION GUTTER HAS



Date Taken: 8/14/2025

FRONT ELEVATION GUTTER HAS

HAIL DAMAGE



38-FRONT ELEVATION

Date Taken: 8/14/2025

FRONT ELEVATION GUTTER HAS



-RIGHT ELEVATION

Date Taken: 8/14/2025 RIGHT ELEVATION HAS NO VISIBLE HAIL DAMAGE



48-RIGHT ELEVATION

Date Taken: 8/14/2025 RIGHT ELEVATION HAS NO VISIBLE HAIL DAMAGE



71-LEFT ELEVATION

Date Taken: 8/14/2025

LEFT ELEVATION HAS NO VISIBLE

QUANTITY	UNIT	TAX	O&P	RCV AGE	E/LIFE		
Asphalt starter - universal starter course							
207.64LF				(0/20 yrs		
2. Tear off composition	shingles - 3 tab	(no haul off)					
64.23 SQ				(0/25 yrs		
3. Laminated - comp. shingle rfg w/out felt							
70.67 SQ				(0/30 yrs		
4. Drip edge							
393.13 LF				(0/35 yrs		
5. Roofing felt - 15 lb.	5. Roofing felt - 15 lb.						
58.23 SQ				(0/20 yrs		
6. lee & water barrier							
622.92 SF				(0/30 yrs		
7. Roof vent - turbine type - Standard grade							
1. 0EA				(0/35 yrs		
8. Flashing - pipe jack							
1							
9. R&R Eavestrough - aluminum - up to 5"*							
102.30LF	8.49	58.19	173.72	1,100.44			

10. Dumpster load - Approx. 30 yards, 5-7 tons of debris

1.00 EA

Grand Total Areas:

0.00	SF Walls SF Floor SF Long Wall	0.00	SF Ceiling SY Flooring SF Short Wall	436.30	SF Walls and Ceiling LF Floor Perimeter LF Ceil. Perimeter
	Floor Area Exterior Wall Area		Total Area Exterior Perimeter of Walls	0.00	Interior Wall Area
- ,	Surface Area Total Ridge Length		Number of Squares Total Hip Length	393.13	Total Perimeter Length